

SEPTIC SYSTEM PERMIT

FLATHEAD CITY-COUNTY HEALTH DEPARTMENT
Environmental Health Services

Number 99-3846R
Site Eval. Receipt 98-1535
Date Issued 7.27.99
Zone 6
Date Recorded 12/6/98

✓ 1. Legal Description: Co. Assess. Tr.# 4G SEC: 20 TWP: 29 RNG: 22
Subdiv. Name _____ Lot _____ Blk. _____
COS # _____ Parcel Size 5 acres

Property Address 527 Grande Vista, Kalispell

✓ 2. Stephen Hooper
Legal Property Owner _____ PO Box 2078, Kalispell
Address and Phone _____

3. Authorization for: New ☐ Replacement of ☒ Alteration/Repair of ☐ Septic System.

4. Proposed Structure: Conv. Sing. Fam. ☒ Mob. Home ☐ Multi-fam. (specify) Conv. Sing. Fam.

Commercial (specify) Conv. Sing. Fam. _____ Other (specify) Conv. Sing. Fam. _____

5. No. of Bedrooms 4 or No. of Occupants _____ Existing Structures _____

6. Water Supply: Indiv. ☒ Multi-user ☐ Public (name) Indiv _____ Source well _____

Evaluator's Comments:

7. Soil Type: stoney loam How Determined: submittal

8. Depth to Groundwater Table/Bedrock >7' How Determined: submittal

System Specifications:

9. Classification 1G Septic Tank Size 1000 gallons (min) Absorption Area 640 ft2

10 Drainfield Description

Use 320 lineal feet of perforated pipe in 2 foot wide trenches. Maximum trench depth shall not exceed 36 inches from the natural ground surface. No single drainline may exceed 80 feet from the point of effluent entry. Plan carefully and be sure of all County septic regulations prior to installation.

The approved drainfield site is on the higher ground adjacent to existing system.

12/21/98
Date

Jere Johnson, R.S.
Signature Authorizing Approval of Permit

* These requirements establish the minimum specifications for this septic system installation. The permit will be voided and declared invalid if the system is not installed within 12 months for class 1, 2, and 4 or 24 months for class 3 and 5 systems. The issuance of this permit authorizes construction of the septic system and requires the installation comply with the FLATHEAD COUNTY REGULATIONS FOR SEWAGE TREATMENT SYSTEMS (FCRSTS). The permit will be void if the system is not utilized as intended within one year of installation. The property owner is responsible for operating and maintaining the system in accordance with FCRSTS. Failure to comply with these regulations may result in revocation of this permit. This permit does not constitute a design and does not bind or obligate this office to guarantee the performance of the system. This permit shall be given to the installer prior to construction. The owner shall give 24hours advance notice for the required inspection of the system. Please call 758-5760.

* 0971701

